Sl No	Descriptions of items	U
206	200x90x65mm	Each
207	135x160x65mm	Each
208	Extra for Groove cutting in brick wall/CC floor to the suitable depth for concealing of Conduit/GI pipe and plastering, finishing upto wall surface complete. with all lead and lift and directions of the Engineer-In-charge of	Mtr
209	upto 50mm conduit CC floor	Mtr
210	Supplying and fixing of PVC casing and capping on the wall or ceiling using necessary materials like bends, screws at an interval of 300mm …. etc. as required.25mm.with all lead and lift and directions of the Engineer-In-	Mtr
211	Supplying PVC/GI flexible conduit pipe…mm dia fixing on surface over inverted tapered wooden plugs or phill plugs or rawl plugs and clamped using heavy gauge saddles at an interval of 300mm using NF screws and on either	Mtr
212	Supplying And Fixing Metal Fan Box with Round Hook.	No
213	Point wiring using Copper wire with switch. Supplying and wiring adopting loop system in existing PVC Conduit / casing capping using 1100V grade, COPPER conductor flexible multistrand FRLS PVC insulated, 2 X1.5Sq.mm	Point
214	Medium point above 3Mtr upto 6Mtr from tapping point to out let via switch	Point
215	Long point above 6Mtr upto 10Mtr from tapping point to out let via switch	Point
216	Two outlet in a row, above 3Mtr upto 6Mtr from tapping point to out let via switches	Point
217	Three outlet in a row, above 6Mts upto 10Mtr from tapping point to out let via switches	Point
218	Wiring for fighting/power circuit using one of FRLS PVC insulated 1100V grade, multistrand Copper with low conductor resistance single core wire in open or concealed system of wiring with specified IS-694:1990 &	Mtr.
219	2.5 sqmm(1500MTRS FOR FIRE ALARM)	Mtr.
220	4 sqmm	Mtr.
221	Supplying and drawing Flexible Multicore Cable manufactured with electrolytic grade flexible copper with low conductor confirming to table 3 class 5 of IS:8130-1984 and (Virgin) PVC insulation and sheathed suitable for	Mtr.
222	4C X 2.5Sq.mm	Mtr.
223	Supplying and fixing superior quality modular switch mounting polycarbonate plate with necessary supporting back plate with required nos. of machine screws, bolts nuts etc., complete on the existing metal/PVC box.with all	Each
224	4 Module	Each
225	6 Module	Each
226	8 Module	Each
227	10 Module	Each
228	12 Module	Each
229	Supplying and fixing of modular switch/ Socket/stepped electronic fan regulator/ dimmer/telephone socket etc on existing modular switch plate as per IS 3854 and IS 1293 GROUP A.with all lead and lift and directions of the	Each
230	6Amps Two way.	Each
231	6Amps 3way socket.	Each
232	Stepped Fan Regulator.	Each
233	6Amps Bell push	Each
234	6/16Amps universal socket	Each
235	TV/Telephone socket	Each
236	Supplying 4mm thick plastic sheet with necessary nitches for fixing switches, regulators etc., and fixing on existing wooden or metal box using N.F. screws.with all lead and lift and directions of the Engineer-In-charge of	Sq C
237	Supplying 50mm wooden plug, tapered from 50x50mm to 25x25mm and fixing by using binding wire before concreting a roof slab.with all lead and lift and directions of the Engineer-In-charge of the work	N
238	Supplying and fixing of metal clad industrial plugs and sockets. PLUG 2pole+earth 250V.with all lead and lift and directions of the Engineer-In-charge of the work 10 Amps	Ea
239	20 Amps	Ea
240	Supplying and fixing of metal clad industrial plugs and sockets. PLUG 3pole+earth 440V.with all lead and lift and directions of the Engineer-In-charge of the work 20 Amps	Ea
241	30 Amps	Ea
242	Supplying and fixing cast Aluminum round or oblong type bulk head fitting with GI wire guard, glass cover with 15Watts 230V CFL lamp.with all lead and lift and directions of the Engineer-In-charge of the work	Ea
243	Supplying surface mounted type mirror optic luminaries for single/Twin 28watts fluorescent lamps cross rising of stove enameled deep coloured M.S.low profile housing complete with all accessories and high purity anodized	Ea

Previous		Present			Total Up to Date		Remarks
Qty	Amount	Qty	Rate	Amount	Qty	Amount	
12.00	1620.00	0.00	135.00	0.00	12.00	1620.00	
98.00	13230.00	0.00	135.00	0.00	98.00	13230.00	
2500.00	75000.00	0.00	30.00	0.00	2500.00	75000.00	
50.00	2250.00	0.00	45.00	0.00	50.00	2250.00	
150.00	5250.00	0.00	35.00	0.00	150.00	5250.00	
500.00	15000.00	0.00	30.00	0.00	500.00	15000.00	
180.00	19800.00	0.00	110.00	0.00	180.00	19800.00	
5.00	1000.00	0.00	200.00	0.00	5.00	1000.00	
198.00	59400.00	0.00	300.00	0.00	198.00	59400.00	
218.00	87200.00	0.00	400.00	0.00	218.00	87200.00	
90.00	45000.00	0.00	500.00	0.00	90.00	45000.00	
75.00	52500.00	0.00	700.00	0.00	75.00	52500.00	
4500.00	99000.00	0.00	22.00	0.00	4500.00	99000.00	
14500.00	507500.00	0.00	35.00	0.00	14500.00	507500.00	
7250.00	362500.00	0.00	50.00	0.00	7250.00	362500.00	
100.00	6500.00	0.00	65.00	0.00	100.00	6500.00	
100.00	12500.00	0.00	125.00	0.00	100.00	12500.00	
33.00	3960.00	0.00	120.00	0.00	33.00	3960.00	
22.00	3080.00	0.00	140.00	0.00	22.00	3080.00	
13.00	2600.00	0.00	200.00	0.00	13.00	2600.00	
264.00	59400.00	0.00	225.00	0.00	264.00	59400.00	
12.00	3000.00	0.00	250.00	0.00	12.00	3000.00	
98.00	29400.00	0.00	300.00	0.00	98.00	29400.00	
976.00	73200.00	0.00	75.00	0.00	976.00	73200.00	
6.00	570.00	0.00	95.00	0.00	6.00	570.00	
396.00	59400.00	0.00	150.00	0.00	396.00	59400.00	
28.00	8400.00	0.00	300.00	0.00	28.00	8400.00	
6.00	600.00	0.00	100.00	0.00	6.00	600.00	
214.00	34240.00	0.00	160.00	0.00	214.00	34240.00	
55.00	5500.00	55.00	100.00	5500.00	110.00	11000.00	
180.00	54.00	0.00	0.30	0.00	180.00	54.00	
4000.00	32000.00	0.00	8.00	0.00	4000.00	32000.00	
10.00	2250.00	0.00	225.00	0.00	10.00	2250.00	
10.00	2500.00	0.00	250.00	0.00	10.00	2500.00	
10.00	3000.00	0.00	300.00	0.00	10.00	3000.00	
10.00	3250.00	0.00	325.00	0.00	10.00	3250.00	
10.00	10000.00	0.00	1000.00	0.00	10.00	10000.00	
50.00	150000.00	0.00	3000.00	0.00	50.00	150000.00	

Sl No	Descriptions of items	
244	Supplying CFL mirror light fitting with 1x11W CFL lamp, choke, Perspex cover and completely wired for use on 230V 50Hz AC supply.with all lead and lift and directions of the Engineer-In-charge of the work	Each
245	Supply of recess mounted rolling type LED square or round Down light 12 watts with 4/6W GU 10 LED Lamp Rib Fabricated from Die cast aluminum with white powder coated prewired to mains connector with suitable driver &	No
246	Supply of LED Square Recessed Down lighter with 18W System Wattage. Housing shall be with powder coated pressure die cast aluminum alloy with corrosion resistant polyester powder coat & with extended heat sink.	No
247	Supplying and fixing of round or oblong type bulk head fitting glass cover.with all lead and lift and directions of the Engineer-In-charge of the work	No
248	Supplying and fixing miniature circuit breakers on existing MCB distribution boards using necessary fixing materials and 'C' Type curve, indicator ON/OFF, energy cross-3 with Short circuit breaking capacity of 10K and	Each
249	5-32 Amps DP	Each
250	40-63Amps TPN	Each
251	Supplying and fixing regular MCB distribution boards on wall / wood board / flush mounting using required clamps, bolts, nuts etc., with provision for fixing suitable type capacity MCB's single phase / 3 phase / single door	Each
252	12Way SP &N	Each
253	Supplying and fixing regular MCB distribution boards on wall / wood board / flush mounting using required clamps, bolts, nuts etc., with provision for fixing suitable type capacity MCB's single phase / 3 phase / single door	Each
254	8Way TP &N	Each
255	Supplying, fixing and wiring Earth Leakage Miniature Circuit Breaker [ELMCB] 240/450V up to 300mA sensitivity on existing wood/panel board.with all lead and lift and directions of the Engineer-In-charge of the work	Each
256	32-40 Amps 4 pole	Each
257	63 Amps 4 pole	Each
258	Supplying and fixing of Metal Socket set of 2pole and earth plugs and socket for incorporating SP and TP MCB (Without MCB). The entire plug and socket shall be mounted in a thermoplastic / powder coated metal box &	Each
259	30Amps	Each
260	LT KIOSK INCOMER :	Set
261	MAIN PANEL EB INCOMER :	Set
262	GROUND FLOOR PANEL INCOMER :	Set
263	FIRST FLOOR PANEL INCOMER :	Set
264	SECOND FLOOR PANEL INCOMER :	Set
265	COMMON SERVICE PANEL INCOMER :	Set
266	APFC PANEL (60kVAR) INCOMER :	Set
267	Supplying, fixing, wiring, earth electrode for grounding conduits, I.C. cutouts and other equipment's on the meter board using 40mm dia 2.90mm thick GI pipe 2.5 mtr long buried in a pit … The pit should be filled with equal	No
268	Supplying fixing and wiring earth electrode for grounding of lifts, transformers, DG Set etc. using 40mm dia 2.9mm thick 2.5 mtr long GI pipe with GI funnel with mesh and suitable size reducer fixed on the top of the earth	No
269	Supplying and running of GI/Copper strips for grounding connections, using necessary fixing materials as required. GI strip.with all lead and lift and directions of the Engineer-In-charge of the work 25x6mm	Mtr
270	40x6mm	Mtr
271	600x600x3mm GI Plate	Each
272	Supplying and running of GI/Copper strips for grounding connections, using necessary fixing materials as required. 25x3mm Copper strip.with all lead and lift and directions of the Engineer-In-charge of the work 25x3mm	Mtr
273	600x600x3mm plate	Each
274	Supplying of 1.1 KV LT UG cable having aluminum conductor PVC insulated, extruded inner sheathed, galvanized, steel strip (except 2CX10Sq.mm wire armoured) confirming to IS-3975:1990 (No. of Strip indicated in	Mtr
275	4 core 10 sqmm	Mtr
276	4 core 16 sqmm	Mtr

Previous		Present			Total Up to Date		Remarks
Qty	Amount	Qty	Rate	Amount	Qty	Amount	
20.00	14000.00	0.00	700.00	0.00	20.00	14000.00	
375.00	750000.00	0.00	2000.00	0.00	375.00	750000.00	
200.00	1020000.00	0.00	5100.00	0.00	200.00	1020000.00	
10.00	650.00	0.00	65.00	0.00	10.00	650.00	
140.00	63000.00	0.00	450.00	0.00	140.00	63000.00	
10.00	9000.00	0.00	900.00	0.00	10.00	9000.00	
10.00	20000.00	0.00	2000.00	0.00	10.00	20000.00	
9.00	12150.00	0.00	1350.00	0.00	9.00	12150.00	
3.00	5250.00	0.00	1750.00	0.00	3.00	5250.00	
14.00	35000.00	0.00	2500.00	0.00	14.00	35000.00	
4.00	14800.00	0.00	3700.00	0.00	4.00	14800.00	
11.00	30800.00	0.00	2800.00	0.00	11.00	30800.00	
6.00	18000.00	0.00	3000.00	0.00	6.00	18000.00	
12.00	42000.00	0.00	3500.00	0.00	12.00	42000.00	
10.00	12500.00	0.00	1250.00	0.00	10.00	12500.00	
10.00	17500.00	0.00	1750.00	0.00	10.00	17500.00	
1.00	230000.00	0.00	230000.00	0.00	1.00	230000.00	
1.00	630000.00	0.00	630000.00	0.00	1.00	630000.00	
1.00	95000.00	0.00	95000.0	0.00	1.00	95000.00	
1.00	60000.00	0.00	60000.00	0.00	1.00	60000.00	
1.00	60000.00	0.00	60000.00	0.00	1.00	60000.00	
1.00	68000.00	0.00	68000.00	0.00	1.00	68000.00	
1.00	100000.00	0.00	100000.00	0.00	1.00	100000.00	
10.00	30000.00	0.00	3000.00	0.00	10.00	30000.00	
8.00	36000.00	0.00	4500.00	0.00	8.00	36000.00	
500.00	62500.00	0.00	125.00	0.00	500.00	62500.00	
75.00	13500.00	0.00	180.00	0.00	75.00	13500.00	
8.00	6400.00	0.00	800.00	0.00	8.00	6400.00	
75.00	41250.00	0.00	550.00	0.00	75.00	41250.00	
6.00	43500.00	0.00	7250.00	0.00	6.00	43500.00	
650.00	61750.00	0.00	95.00	0.00	650.00	61750.00	
650.00	87750.00	0.00	135.00	0.00	650.00	87750.00	
950.00	142500.00	0.00	150.00	0.00	950.00	142500.00	

Sl No	Descriptions of items	U
277	3.5 core 25 sqmm	Mtr
278	3.5 core 50 sqmm	Mtr
279	3.5 core 70 sqmm	Mtr
280	3.5 core 240 sqmm	Mtr
281	Labour charges for laying of 1.1 KV class UG cable in existing trench GI pipe / stoneware pipe / on wall / on pole as required.In existing trench/duct.with all lead and lift and directions of the Engineer-In-charge of the work 6	Mtr
282	25 sqmm to 75 sqmm	Mtr
283	95 sqmm to150Sqmm	Mtr
284	Digging of trench of 0.6m deep x 0.50 mtr wide refilling the trench to the required ground level and consolidating etc., complete.(As per Civil SR KSRB I-2, P-7) In soil (ordinary) with all lead and lift and directions of the	Mtr
285	Supplying and fixing of heavy duty cable glands suitable for UG cable of 1.1 KV class (metal only) with all lead and lift and directions of the Engineer-In-charge of the work 25mm dia	Each
286	32mm dia	Each
287	45mm dia	Each
288	63mm dia	Each
289	Supplying and fixing 2mm thick perforated cable tray with powder coated paint on existing MS angle support using necessary GI bolts/nuts and washer or welding as required.750x50mm with all lead and lift and directions of	Mtr
290	Supplying tinned copper lugs and crimping and wiring to terminal point for wire of the following sizes.with all lead and lift and directions of the Engineer-In-charge of the work 10 sqmm	Each
291	16 sqmm	Each
292	25 sqmm Long Barrel	Each
293	50 sqmm Long Barrel	Each
294	70 sqmm Long Barrel	Each
295	150 sqmm Long Barrel	Each
296	240 sqmm Long Barrel	Each
297	Supplying and running GI/Copper conductor for grounding and (along with other wires in conduit system of wiring) using necessary suitable size clamps, nails, guttas/spacers etc. Copper wire.8 SWG.with all lead and lift	Mtr
298	Supplying exhaust fan of 1440 RPM of 300mm (12") size with bracket blades complete for light duty suitable to operate on 230V 50Hz, AC Supply.with all lead and lift and directions of the Engineer-In-charge of the work	Each
299	Supplying capacitor type ceiling fan complete with down rod blades, shackle, canopies etc., for operation on 230 volts, 50 cycles. Single phase AC supply conforming to ISS-374-1979 and with double ball bearing system. 56"	Each
300	Supplying wall mounting fan suitable to operate at single-phase 230v A.C. supply.400mm Sweep.with all lead and lift and directions of the Engineer-In-charge of the work	Each
301	Supplying and drawing UTP-CAT 6E LAN cable.with all lead and lift and directions of the Engineer-In-charge of the work	MT.
302	Supplying and drawing PVC flexible one pair telephone unarmoured tinned copper cable.2Pair.with all lead and lift and directions of the Engineer-In-charge of the work	Rmt.
303	Supplying and drawing PVC insulated gas injected physical foam jelly flooded co-axial TV cable.RG-6.with all lead and lift and directions of the Engineer-In-charge of the work	Rmt.
304	Supplying, erecting, testing & commissioning of OFF-LINE UPS system suitable for operation on 230V, 50Hz. A/C supply, with all accessories complete and Excluding batteries and wiring complete.5 KVA OFF LINE UPS	Each
305	Supplying, installation, testing & commissioning of 12Volts ..AH batteries in poly propylene container for D.G. Set Low maintenance batteries, plate type.120 AH capacity. Acid batteries.with all lead and lift and directions of	Each
306	Supplying, erection, testing and commissioning of .....KVA Diesel Generating Set on existing CC platform Comprising of Diesel Engine Developing ..... BHP @ 1500 RPM confirming to BS 5514.The engine should be	Each
307	Supply, Erection, testing and commissioning of AMF panel suitable for .....KVA DG Set The panel is of cubical type base/floor mounting control panel with hinged doors, undrilled bottom gland plate, aluminum Bus Bar with	Each
308	Filtering of oil in the transformer at the transformer center by hot process using "Stream line filter" such time the dielectric strength of the oil in the transformer conforms to ISI specification [Test certificate to be produced]with	Litre
309	Supplying and Topping -up of new Transil OIL	Per Litr
310	Supplying and filling fresh silica gel to the breather of transformers.	Per breathe
311	Supplying and Testing of OIL for Di-Electric strength (BDV) / Acidity	Per Sampl
312	Fixing all types and all capacities of fluorescent / false ceiling / spot light / CFL / LED fittings indoor on the wall / ceiling / rafters / girders using 23/0.0076" twin twisted PVC insulated wires, required Nos of round blocks and	Each

Previous		Present			Total Up to Date		Remarks
Qty	Amount	Qty	Rate	Amount	Qty	Amount	
120.00	21600.00	0.00	180.00	0.00	120.00	21600.00	
280.00	84000.00	0.00	300.00	0.00	280.00	84000.00	
25.00	7500.00	0.00	300.00	0.00	25.00	7500.00	
100.00	125000.00	0.00	1250.00	0.00	100.00	125000.00	
2250.00	33750.00	0.00	15.00	0.00	2250.00	33750.00	
425.00	8500.00	0.00	20.00	0.00	425.00	8500.00	
100.00	3000.00	0.00	30.00	0.00	100.00	3000.00	
100.00	8500.00	0.00	85.00	0.00	100.00	8500.00	
60.00	5700.00	0.00	95.00	0.00	60.00	5700.00	
8.00	1200.00	0.00	150.00	0.00	8.00	1200.00	
2.00	500.00	0.00	250.00	0.00	2.00	500.00	
14.00	7000.00	0.00	500.00	0.00	14.00	7000.00	
50.00	62500.00	0.00	1250.00	0.00	50.00	62500.00	
36.00	360.00	0.00	10.00	0.00	36.00	360.00	
24.00	360.00	0.00	15.00	0.00	24.00	360.00	
2.00	60.00	0.00	30.00	0.00	2.00	60.00	
6.00	420.00	0.00	70.00	0.00	6.00	420.00	
2.00	300.00	0.00	150.00	0.00	2.00	300.00	
2.00	520.00	0.00	260.00	0.00	2.00	520.00	
14.00	7000.00	0.00	500.00	0.00	14.00	7000.00	
360.00	45000.00	0.00	125.00	0.00	360.00	45000.00	
20.00	37000.00	0.00	1850.00	0.00	20.00	37000.00	
165.00	363000.00	0.00	2200.00	0.00	165.00	363000.00	
20.00	53000.00	5.00	2650.00	13250.00	25.00	66250.00	
600.00	18000.00	0.00	30.00	0.00	600.00	18000.00	
2300.00	41400.00	0.00	18.00	0.00	2300.00	41400.00	
500.00	22500.00	0.00	45.00	0.00	500.00	22500.00	
6.00	36000.00	0.00	6000.00	0.00	6.00	36000.00	
30.00	600000.00	0.00	20000.00	0.00	30.00	600000.00	
1.00	900000.00	0.00	900000.00	0.00	1.00	900000.00	
1.00	140000.00	0.00	140000.00	0.00	1.00	140000.00	
200.00	6000.00	0.00	30.00	0.00	200.00	6000.00	
100.00	20000.00	0.00	200.00	0.00	100.00	20000.00	
1.00	150.00	0.00	150.00	0.00	1.00	150.00	
1.00	250.00	0.00	250.00	0.00	1.00	250.00	
650.00	81250.00	35.00	125.00	4375.00	685.00	85625.00	

Sl No	Descriptions of items	
313	Fixing a ceiling / Wall mounting fan of all capacities and all types to the existing 'S' hook with fan regulator to the existing board together with supplying and fixing 5 amps. ceiling rose, necessary length of 23 / 0.0076 inch PVC	Each
314	Fixing one exhaust fan in the nitch already left in the wall with bolts and nuts and 5 amps. ceiling rose with sufficient length of 23 / 0.0076 inch PVC insulated twin core wire.with all lead and lift and directions of the	Each
315	Providing Supplying and Commissioning of WASHER EXTRACTOR MAKE : RAMSONS/Equivalent MODEL : RVWE - 45 CAPACITY : 45 Kgs HEATING : ELECTRIC for washing bed linen such as bedsheet,pillow covers and patient gowns Dimension : (1350x1400x1750 mm) Approved Rates	No
316	Providing Supplying and Commissioning of WASHER EXTRACTOR MAKE : RAMSONS/Equivalent MODEL : RVWE - 10 CAPACITY : 10 Kgs HEATING : ELECTRIC For washing OT / Infected linen Dimension : (930x970x1355 mm) Approved Rates	No
317	Providing Supplying and Commissioning of TUMBLE DRIER MAKE : RAMSONS/Equi9valent MODEL : RVWE - 45 CAPACITY : 45 Kgs HEATING : ELECTRIC for drying bed linen such as patient gowns etc.,(1050x1320x1870 mm) Approved Rates	No
318	Providing Supplying and Commissioning of TUMBLE DRIER MAKE : RAMSONS/Equi9valent MODEL : RTD - 15 CAPACITY : 15 Kgs HEATING : ELECTRIC for drying OT/infected linen (830x1270x1490 mm) Approved Rates	No
319	Providing Supplying and Commissioning of FLAT WORK IRONER MAKE : RAMSONS/Equi9valent ROLLER LENGTH : 1600 MM ROLLER DIA: 250 MM HEATING : ELECTRIC for drying bed linen such as bedsheet, pillow covers (830x1270x1490 mm) Approved Rates	No
	Grand Total RS	

Previous		Present			Total Up to Date		Remarks
Qty	Amount	Qty	Rate	Amount	Qty	Amount	
180.00	27000.00	0.00	150.00	0.00	180.00	27000.00	
20.00	10000.00	0.00	500.00	0.00	20.00	10000.00	
1.00	1450000.00	0.00	1450000.00	0.00	1.00	1450000.00	
1.00	514000.00	0.00	514000.00	0.00	1.00	514000.00	
1.00	450000.00	0.00	450000.00	0.00	1.00	450000.00	
1.00	360000.00	0.00	360000.00	0.00	1.00	360000.00	
1.00	650000.00	0.00	650000.00	0.00	1.00	650000.00	
	29700752.35			3027072.16		32727824.51	

Rs: 2.97,00.098-00

Rs: 3.27,27,170-00